Global Academic Journal of Economics and Business

Available online at https://www.gajrc.com
DOI: https://doi.org/10.36348/gajeb.2026.v08i06.003

OPEN ACCESS



ISSN: 2706-9001 (P)
ISSN: 2707-2584 (O)

Original Research Article

Enhancing the Resilience of Critical Industrial Buildings and Infrastructure in Saudi Arabia through Redundant UPS Systems, Automatic Power Transfer and Emergency Supply Continuity

Abubakar Moosa Shaikh[1]*
[1]Independent Researcher

***Corresponding Author**
Abubakar Moosa Shaikh
Independent Researcher

Article History
Received: 29.08.2026
Accepted: 26.10.2026
Published: 03.11.2026

Abstract: Industrial buildings depend on electrical services whose interruption can disable process protection, ventilation, communications, security and emergency response. Saudi Arabia's expanding industrial infrastructure therefore requires power continuity strategies that address both routine equipment faults and prolonged external disruptions. This review critically synthesises research published between 2020 and 2025 on redundant uninterruptible power supplies, automatic power transfer, standby generation and associated control systems. Sources were examined through a structured, topic-led integrative review and evaluated against failure independence, transfer behaviour, autonomy, maintainability and service restoration. The synthesis finds that additional equipment cannot guarantee resilience when redundancy shares batteries, switchgear, cooling, control logic or maintenance exposure. Furthermore, an automatic transfer switch normally introduces an interruption; genuinely interruption-sensitive loads require an appropriately configured online UPS or equivalent ride-through provision. A layered architecture is proposed in which independently protected load paths are coordinated with verified source-transfer sequences, conditioned battery capacity and tested emergency generation. The review extends infrastructure-scale resilience principles to facility-level electrical interfaces and identifies measurable acceptance criteria for industrial applications in Saudi Arabia. Evidence gaps include sparse local field performance records, limited joint modelling of transfer and battery failures, and insufficient validation under compound heat, dust and utility disturbances. These findings provide a design and assurance agenda rather than an assertion of measured performance at any particular site.

Keywords: Critical Industrial Buildings, Infrastructure Resilience, Redundant UPS, Automatic Transfer Switch, Emergency Power, Saudi Arabia, Power Continuity.

Copyright © 2026 The Author(s): This is an open-access article distributed under the terms of the Creative Commons Attribution **4.0 International License (CC BY-NC 4.0)** which permits unrestricted use, distribution, and reproduction in any medium for non-commercial use provided the original author and source are credited.

1. INTRODUCTION

Critical industrial buildings are not simply enclosed production spaces. They contain the electrical and digital functions that keep processes within safe operating limits, coordinate protective shutdowns and preserve the capability to recover after a disturbance. A loss of power may stop pumps and compressors immediately, but its more consequential effects can emerge through unavailable instrumentation, disabled cooling,

inaccessible control rooms or failed communications. As industrial systems become interconnected, apparently local faults can cross physical and operational boundaries. Recent energy resilience literature consequently distinguishes the ability to withstand disruption from the narrower probability of satisfactory operation during ordinary conditions [1–4].

In Saudi Arabia, this distinction matters for petrochemical facilities, utilities, logistics complexes, desalination infrastructure, industrial campuses and digitally intensive manufacturing. Expansion and diversification under Vision 2030 increase the significance of dependable operational services, while ambient heat, airborne dust and geographically dispersed assets complicate equipment assurance. These factors should inform engineering design without implying that every Saudi location experiences identical exposure. Research on power-system resilience highlights the need to combine infrastructure hardening with operational recovery, rather than treat either as an independent solution [5–7]. The building-level implications are particularly important where a process can withstand a brief voltage disturbance but cannot tolerate a loss of control or emergency ventilation.

Conventional emergency power designs often describe a utility supply, a standby generator and a changeover device. Such descriptions conceal the actual sequence through which critical loads remain energised. Starting a diesel generator takes time, switching a source can involve an open interval, and a nominally redundant UPS can still depend on a single upstream panel. Research on generator performance shows that availability at the beginning of an outage, successful starting and sustained operation are distinct reliability questions [11, 12]. Facility owners therefore need an explanation of power continuity at the load terminals, not an inventory of installed equipment.

The aim of this review is to develop an evidence-informed framework for strengthening emergency electrical supply continuity in critical Saudi industrial buildings. Its objectives are to distinguish service continuity from component redundancy; critically compare UPS and source-transfer arrangements; explain battery and generator coordination under compound failures; and establish a verification framework connecting technical design, maintenance and recovery. The contribution lies in integrating device-level power electronics with building-level functional resilience. No site-specific outage data, reliability simulation or experimental commissioning is claimed. Instead, engineering propositions are separated from reported findings so that their transferability remains transparent.

2. REVIEW METHODOLOGY AND ANALYTICAL BASIS

A critical integrative review was adopted because the research question spans electrical power conversion, switching logic, storage degradation, emergency generation and interdependent infrastructure. A purely statistical aggregation would be misleading: the relevant studies evaluate markedly different load classes, disturbance definitions, battery technologies and observation periods. The review considered research issued from January 2020 through December 2025 and prioritised peer-reviewed studies, technical reviews and a directly relevant electrical engineering standard possessing traceable digital identifiers. Search concepts combined resilience, critical buildings, UPS redundancy, automatic transfer, emergency supply, battery autonomy, generator reliability, microgrids and Saudi operating conditions.

Material was identified through publisher records, scholarly indexing and institutional research repositories. Relevance screening required an explicit connection to one or more of five themes: interruption-sensitive loads, source diversity, failure propagation, backup energy endurance or validation of continuous service. Publications dealing only with general renewable penetration, without a meaningful continuity implication, received lower analytical weight. Research on hospitals, data centres and airports was retained when it examined electrical functions transferable to industrial buildings; its findings were not presented as direct Saudi industrial measurements. Foundational concepts were interpreted through the chosen 2020–2025 corpus, and the thematic synthesis drew on thirty DOI-linked works [1–30].

Extraction proceeded conceptually rather than through an invented quantitative dataset. For each source, the assessment considered system boundary, initiating hazard, available supply paths, fault assumptions, claimed performance measure and limitations of application. Findings were compared using four layers: resistance before disruption, uninterrupted support during transition, extended supply following transition and controlled restoration. Disagreements were resolved through engineering scope: an architecture can be resilient to loss of one UPS module without being resilient to failure of a shared battery room. Such conditional interpretation follows recent calls for resilience metrics that identify the service being protected and the event over which protection is evaluated [2-6].

The evidence base supports a qualitative design framework, not a calculated prediction of site availability. A literature citation showing improved outage survivability under a particular generator network cannot be converted into a universal percentage for a different plant. Likewise, no documentary method can establish compliance with a current local electrical code, protection settings or manufacturer transfer limitations. These require project-specific technical review. This explicit boundary is important because design recommendations otherwise acquire an appearance of precision that the published evidence cannot justify.

3. Electrical Resilience as a Facility-Level Function

Resilience must be specified at the level of a protected service. A production line, distributed control system, fire alarm panel and emergency lighting network do not have the same tolerable interruption or restoration sequence. The first design task is therefore a critical-load schedule linking each circuit to consequences, allowable disturbance, minimum operating period and controlled shutdown requirements. A single category labelled essential can obscure differences between equipment requiring effectively continuous alternating-current supply and motors that may safely restart after a planned delay. This service perspective is consistent with wider reviews of disturbance severity and restoration metrics [1–4].

Reliability and resilience also require different evidence. Mean time between failures is useful for comparing maintainable components under assumed operating conditions, but it does not describe how several elements behave during a common-cause incident. A major heat event, flooded switch room, control network failure or mistaken isolation can remove supposedly independent paths simultaneously. Quantitative work on infrastructure interdependence demonstrates that network coupling changes the effects of disturbance relative to analysis of isolated assets [22, 23]. Critical load continuity should therefore be assessed through the entire route from source to terminal, including protection, switchboards, cable routes, power conversion and environmental support.

A practical service metric is the proportion of protected load supplied throughout an explicitly defined outage interval. Further indicators include the longest unserved interval at the load, expected energy not supplied, probability of successful generator acceptance, reserve battery endurance and time to recover normal selective protection. These measures should be recorded by load tier and scenario rather than collapsed into one availability figure. A system may restore its aggregate megawatt demand promptly while failing a small safety controller whose loss dominates the consequence. Recent reviews similarly argue that restoration speed and infrastructure performance must be measured together [2-7].

Three classes of event should guide the evaluation. First, local equipment faults challenge module redundancy and downstream discrimination. Second, source disturbances challenge detection settings, synchronization and stored-energy ride-through. Third, prolonged disturbances challenge fuel logistics, battery ageing, cooling, access and organisational capacity. The same installed equipment may perform very differently across the classes. The design question is not whether an alternative supply exists in the drawings, but whether usable electrical power can reach the correct load during each credible failure and subsequent maintenance state.

4. Redundant UPS Architecture and Failure Containment

An uninterruptible power supply is a power-conditioning system, not merely a battery attached to an industrial switchboard. In an online double-conversion arrangement, the rectifier and inverter normally maintain the protected output while stored energy supports the direct-current link when the input disappears. The resulting ride-through function is valuable for programmable logic controllers, supervisory systems, network infrastructure and selected protection devices. However, its continuity depends on the inverter, static bypass, battery path and downstream distribution remaining within design limits. Research on battery autonomy and power-device condition monitoring reinforces the need to examine these elements as ageing electrical assemblies rather than permanent nameplate capacities [16-20].

A basic N architecture provides sufficient capacity during normal conditions but little tolerance for a module outage. N+1 arrangements add modular capacity so that the design load can be sustained after one module is unavailable, assuming distribution and supporting systems remain healthy. Parallel modules may nevertheless share a switchboard, control bus, bypass feeder or cooling failure mode. A distributed 2N architecture provides two separately rated UPS paths with independent components, while a dual-corded load can obtain supply through diverse terminal feeds. These are not interchangeable labels: the degree of independence has to be proved across upstream and downstream interfaces. Reviews of resilience and microgrid design warn against equating redundant equipment counts with independent service routes [8, 9].

Common-cause protection should begin with physical and electrical segregation. Separate battery isolators, suitably independent upstream breakers, independent auxiliary supplies and diverse cable routes reduce exposure to a single event. Where two UPS trains feed a single-corded device, a properly engineered static transfer arrangement may be required; the switching device must be evaluated for source synchronization, fault withstand, transfer time and load compatibility. The two inputs must not be connected through a hidden common bypass or maintenance connection that defeats the intended separation. Fault-tree reasoning is more informative than a simplified multiplication of assumed component reliabilities when common controls or human actions remain shared.

Maintenance bypass design presents a frequent contradiction. The system may meet its nominal redundancy definition during operation, yet a routine inverter service may expose every protected load to raw upstream power. Maintenance states therefore belong in the architecture study. A credible design should support safe isolation of one module, verified continuity on the remaining capacity, and an operating instruction that prevents accidental bridging of independent buses. Batteries must remain accessible for inspection and replacement without compromising the other path. The 2022 battery guidance addresses selection, sizing, maintenance and testing as linked elements of UPS dependability [15].

Battery configuration deserves particular attention because a healthy inverter cannot sustain an outage once usable stored energy has been exhausted. Separate strings are not fully independent if they share a single charging circuit, protective fuse, room temperature controller or inadequate ventilation. Cell imbalance and connector resistance can also alter effective autonomy under high discharge. Experimental autonomy estimation research demonstrates that battery behaviour depends on operating conditions and ageing, supporting verification against load and temperature rather than the nominal ampere-hour label [16]. Consequently, continuity assurance should include discharge profiles, end-of-life capacity margins and clear alarms for reduced reserve.

A two-path scheme also requires disciplined load allocation. Motor starting currents, transformer inrush, nonlinear harmonic demand and bypass overload behaviour can disrupt a train that appears adequately rated by steady-state kilowatts. For critical controllers, transient tolerance and permissible waveform distortion should be obtained from equipment requirements. Electrical harmonics have been examined in a Saudi large-facility case, illustrating that the interaction between generation and nonlinear loads matters alongside energy adequacy [25]. The protected-load schedule should therefore link power quality, short-circuit coordination and terminal-level continuity instead of treating them as separate procurement specifications.




Figure 1: Conceptual dual-path critical-load architecture with distinct UPS trains and coordinated recovery sources. Shared generating resources are shown explicitly; the diagram is not an installation single-line drawing

Table 1: Comparative engineering characteristics of continuity architectures (qualitative synthesis)

Architecture	Protected function	Residual exposure	Required evidence
Single UPS (N)	Power conditioning and short outage support	One module or DC path can interrupt the protected load	Document fault bypass behaviour and actual autonomy
Modular N+1 UPS	Maintains rated load following one module loss	Common bypass, switchboard, control or battery exposure	Demonstrate loss-of-one capacity and safe module isolation
Segregated 2N trains	Two independently capable supply paths	Shared sources, rooms or final load interfaces may remain	Trace segregation to terminal and through maintenance
Static transfer interface	Alternative feed for selected single-input loads	Source synchronism, fault clearing and transfer limitations	Test specified interruptions and input compatibility
ATS plus generator and UPS	Bridges generator start and restores extended supply	Finite start success, open transfer gap, fuel exhaustion	Witness timed sequence under representative loads

5. Automatic Transfer and Emergency Supply Coordination

Automatic transfer switching responds to inadequate preferred-source conditions by connecting an alternative supply according to predetermined logic. It does not, by itself, remove the interruption produced by the loss of one source and establishment of another. Open-transition equipment deliberately disconnects before reconnecting; closed-transition equipment operates under restrictive synchronization and operating conditions and cannot be assumed applicable during a dead-source failure. Designs describing an ordinary generator transfer as uninterrupted therefore confuse two different functions. Research exploring multi-source transfer confirms the flexibility of source selection, but the actual continuity outcome depends on sensing, switching and the characteristics of the connected load [14].

The intended sequence begins with a disturbance threshold, not with an indiscriminate response to every voltage fluctuation. Under-voltage, frequency deviation, loss of phase and phase imbalance require detection windows chosen to avoid nuisance transfer while remaining compatible with equipment ride-through. Following a confirmed failure, the controller issues a generator start command or selects an already viable alternative. The automatic transfer switch changes position only when source conditions satisfy interlocking rules. Throughout this interval an online UPS supplies the loads requiring continuous power. Generator acceptance then restores the UPS input, allowing the battery to recharge under a controlled current limit.

This sequence introduces temporal dependencies. If a generator takes longer to become acceptable than the usable battery reserve, interruption remains possible despite technically successful equipment operation. Conversely, excessively rapid retransfer can destabilise operation during utility recovery. Correct coordination therefore specifies a minimum ride-through budget, credible starting delay, transfer time, generator voltage stabilisation, recharge demand and staggered load restoration. The budget should also allow failed-start retries or explicitly define the condition under which a protected process must undergo a safe shutdown. A hospital microgrid study demonstrates why generator, storage and solar resources must be assessed jointly across outage scenarios rather than individually [26].

Selective protection becomes especially important after transfer. Standby generators and inverter-based supplies may contribute lower or differently shaped fault current than a strong utility network. Breakers and protective relays adjusted for utility conditions may consequently operate too slowly or fail to discriminate on the emergency source. The solution is not simply a larger generator; protection settings, generator decrement curves, inverter fault limits and neutral-earthing configurations must be analysed across operating modes. A transfer that maintains voltage but defeats fault clearance cannot be described as resilient. Functional acceptance tests should therefore include representative downstream faults, interlocks and source return conditions wherever safe and practical.

Control-system dependencies also deserve scrutiny. Digital transfer controllers, communicating breakers and microgrid controllers can improve monitoring while introducing network and software vulnerabilities. Cyber-physical microgrid reliability studies show that communications availability can affect overall electrical performance [21]. A resilient transfer system needs a defined local fallback mode, loss-of-communications behaviour, independent control power, secure settings management and event records sufficient to reconstruct a failure.

Manual intervention should remain possible through a controlled procedure rather than an undocumented override that defeats electrical interlocks. These safeguards make automatic transfer a governed process rather than an isolated switchgear feature.




Figure 2: Conceptual transition sequence. Continuous UPS output is a separate performance requirement from successful changeover between upstream sources

6. Storage, Generation and Long-Duration Endurance

UPS autonomy is the time for which required load can be supplied under specified battery conditions. It is not a fixed property of a battery nameplate, because discharge rate, temperature, age, state of charge, inverter efficiency and shutdown threshold alter the usable period. Capacity tests and condition-monitoring trends provide more meaningful assurance than elapsed installation age alone. The literature on lead-acid prediction demonstrates the value of adapting autonomy estimates to observed operation [16], while the UPS failure analysis from a hospital environment illustrates how maintenance process weaknesses can be systematically identified and reduced [17]. Neither study establishes a single suitable autonomy period for every industrial service.

Technology selection also changes the risk profile. Valve-regulated lead-acid batteries are established in standby applications but require ventilation, inspection and planned replacement. Lithium-ion systems can reduce footprint and offer different cycle characteristics, yet they require chemistry-specific battery management, fire protection and thermal controls. Comparative technical discussion distinguishes lithium iron phosphate from nickel-rich chemistries on discharge response, thermal stability and calendar ageing [18]. Reviews of energy-storage incidents caution that compliance testing alone does not eliminate thermal runaway risk and that facility-level separation and emergency procedures remain necessary [19]. In high-temperature environments, battery-room cooling becomes part of the critical supply chain.

A standby generator converts stored fuel into electrical energy for periods extending beyond the intended UPS bridge. Its resilience contribution must be expressed through separate probabilities of being available, starting, accepting load and running continuously. Analysis of emergency generators provides empirical grounds for treating these probabilities as finite; their deterioration with outage duration can outweigh optimistic assumptions about installed generating capacity [11]. Subsequent comparisons indicate that sharing properly managed resources across a network can improve long-duration service under specific assumptions [12]. Such benefits depend upon distribution survivability and do not remove the possibility of common generator-room, fuel or control failures.

Fuel resilience requires more than storage-volume calculation. Fuel quality, transfer pumps, day tanks, filtration, replenishment arrangements and emergency access are part of the endurance model. A nominally sufficient tank becomes irrelevant if electrical controls for the fuel pump depend on the failed distribution system. Likewise, a generator may be mechanically available but unable to carry chilled-water starting transients or a large UPS recharge step. Project testing should reproduce credible loading sequences and establish shedding priorities for non-critical loads. Research on integrated building emergency power systems suggests that shared resources can improve utilisation, but

optimisation must preserve the capacity reserved for emergency duty [13].

Additional photovoltaic or battery resources may extend supply duration when they are designed to operate in the intended islanded mode. Their contribution must not be treated as a firm substitute for protected inverter capacity without evidence of control stability and resource availability. Reviews of microgrids describe the potential for resilience enhancement alongside protection and operational complexity [9-30]. A data-centre study on coordinated supply and storage illustrates useful optimisation opportunities [27], although operational cost improvements are not equivalent to proven zero-interruption performance. The appropriate design hierarchy is therefore safety continuity first, endurance second and energy optimisation only within validated boundaries.

7. Application to Saudi Industrial Environments

Translation of international evidence into Saudi industrial practice requires attention to both environmental exposure and facility purpose. High seasonal ambient temperatures place sustained demands on UPS electronics, generator cooling and battery-room environmental control. Dust infiltration can obstruct ventilation, degrade contact surfaces and increase maintenance frequency, particularly where filtration and enclosure protection are poorly matched to site conditions. These are design hazards to evaluate, not evidence that every Saudi installation already suffers from a particular defect. A local study of hybrid microgrid supply in Al Uyaynah demonstrates the relevance of resource sizing and continuous service requirements, although its assumptions cannot stand in for an industrial site acceptance test [24].

Industrial geography produces another distinction. A compact plant may have two nominal grid feeders supplied from the same upstream substation, while a remote campus may depend on a long distribution spur. Source diversity must be established by tracing the complete electrical topology and not inferred from a drawing containing two incomers. For shared utility corridors, the risk assessment should address flooding, excavation, fire spread and access restrictions. Recent infrastructure resilience assessments and interdependency models underline why geographically concentrated assets can propagate disruption across services [22-28]. The facility study should explicitly identify common substations, transformer rooms, fuel routes and communication nodes.

The economic evaluation should likewise consider avoided consequence rather than compare capital cost alone. For a critical shutdown system, the value of uninterrupted operation may concern worker safety and environmental containment before production loss. For a packaging line, a short stoppage may have primarily commercial consequences. This differentiation supports tiered investment: duplicated online UPS trains for the most sensitive controls, supported transfer and generation for essential process equipment, and managed restart for deferrable loads. Research on airport microgrid dispatch and resilience illustrates how protected load prioritisation can shape investment appraisal [10]. Outcomes should nevertheless be evaluated with Saudi project costs, actual load records and local maintenance capabilities.

8. Proposed Assurance Framework and Testable Propositions

The proposed framework links five decisions. First, owners establish the consequences and tolerable interruption for each protected service. Second, designers map the complete source-to-load architecture, flagging shared dependencies and maintenance bypass states. Third, a sequence-of-events study confirms the required relationship between UPS support, source qualification, transfer, generator loading and battery recharge. Fourth, a scenario-based endurance study addresses short faults, repeated disturbances and extended outages. Fifth, evidence from commissioning and periodic testing is recorded against the original service requirement. Figure 1 depicts the resulting layered architecture, while Figure 2 expresses the sequence as a continuity state model.

Assurance should use falsifiable acceptance criteria. For each interruption-sensitive load, the test record should specify allowable output deviation and maximum interruption, measured at its terminals rather than inferred from breaker position. For each UPS train, evidence should demonstrate isolation of a failed module without exceeding remaining capacity. For each automatic transfer arrangement, testing should record detection delay, interlock behaviour, source qualification and unsuccessful-start response. For each generator, the record should cover loading, extended running and return-to-normal logic. The construction of these evidence chains follows the broader literature's movement towards explicit, scenario-dependent resilience metrics [2-28].

Four propositions emerge for future investigation. First, verified electrical separation should predict protected-load continuity more strongly than nominal module count. Second, battery reserve should be evaluated as a distribution of usable endurance, especially where environmental temperature and maintenance vary. Third, transfer-related failures should be modelled jointly with generator start failures, because neither hazard is

independent of the timing sequence. Fourth, maintenance and controls should be represented as active parts of resilience, rather than administrative variables applied after equipment selection. These propositions can be tested through anonymised event logs, commissioning reports and asset-level performance histories from Saudi industrial facilities.

A suitable comparative study would stratify facilities by load criticality, system architecture and geographic exposure. Researchers could then analyse observed transfer performance, battery discharge outcomes and restoration intervals without publishing sensitive plant schematics. The outcome measures should include maximum critical-load interruption, expected energy not supplied, successful autonomous transition and safe shutdown completion. Research on power-outage impacts demonstrates the value of viewing electrical disruption through both technical and service consequences [29]. Without this multidisciplinary measurement, projects may overstate resilience by reporting generator starts while overlooking failed controls or unacceptable transient voltage excursions. An important distinction is the treatment of latent failures. A standby component may appear available for months because it has not been asked to operate under demand. Periodic exercise should therefore include actual mechanical actuation, instrumented load response and the relevant alarm-to-action pathway. Evidence from generator research shows why successful starts do not guarantee sustained operation [11, 12]. For power electronics, monitoring trends should be linked to actionable thresholds and formal corrective work orders, not retained as isolated dashboard indicators [17-20].

Electrical fault containment also places boundaries on source sharing. A bus tie may improve flexibility, but it can expose both trains to one protection error or arc-flash incident. Conversely, permanently segregated systems can create avoidable difficulties during planned maintenance if alternative routes cannot be verified. Design reviews must examine both operational diagrams and switching procedures, including lockout, position indication and restoration authority. The preferred arrangement is therefore determined by consequence and proof of isolation, not by assuming either complete interconnection or separation is universally optimal.

For battery systems, reserve duration must be defined at an end-of-service condition rather than only at commissioning. A useful evaluation distinguishes energy needed to bridge normal generator starting, margin for an unsuccessful first attempt and energy retained for a controlled shutdown. Each portion depends on discharge capability at the stated temperature and load. Where generator failure triggers load shedding, the selected sequence should preserve instrumentation and emergency communication until the final safety action is confirmed. This is a functional safety requirement, not simply an efficiency measure.

The proposed review also has a practical procurement implication. Equipment schedules often state capacity and nominal redundancy while leaving transfer timing, alarm supervision, bypass configuration and replacement access in narrative specifications. Contract documents should instead connect each requirement to a test method and acceptance evidence. Independent witnesses can verify that the installed arrangement reflects the approved single-line diagram, that settings match the protection study and that operating teams can recover safely from a failed automatic sequence. Such documentary discipline reduces the gap between design intent and long-term facility performance.

Finally, assurance should continue after handover. Seasonal performance checks, updated critical-load inventories, battery-health trending, generator fuel inspections and controlled drills help reveal drift from the original assumptions. An additional server cabinet or modified ventilation unit can consume the very redundancy margin intended for fault survival. Asset changes should trigger re-evaluation of steady-state loading, transient behaviour and achievable autonomy. A facility should be called resilient only for the scenarios it has analysed and the service outcomes it can demonstrate.

A further research priority concerns event chronology. Existing summaries frequently report whether the standby source became available without preserving the milliseconds surrounding load loss, UPS inverter response and transfer initiation. Time-synchronised waveform capture at selected critical terminals would allow investigators to distinguish voltage sag tolerance from genuine supply continuity. Pairing these records with generator start logs, battery condition and protective relay events could reveal sequences otherwise misclassified as unrelated equipment defects. The resulting evidence should be anonymised and grouped by equipment duty, event severity and maintenance state before wider comparison. This approach would support causal investigation without presenting proprietary industrial schematics, while creating stronger evidence for future performance specifications and context-specific design guidance in Saudi facilities and procurement decisions.

Table 2: Scenario-based commissioning and lifecycle assurance matrix for essential electrical services

Failure scenario	Failure mechanism	Minimum functional safeguard	Acceptance / follow-up evidence
Preferred utility source fails	Loss of input and changeover delay	UPS output remains within load tolerance; ATS qualifies alternative	Time-stamped output waveform and switching event record
One UPS module is isolated	Capacity margin and shared bypass risk	Remaining train or modules sustain the specified critical tier	Witnessed isolation and load-sharing test
Standby generator fails to start	Battery reserve may become insufficient	Alarm, retry or safe shutdown executes within usable autonomy	Failed-start simulation plus measured reserve
Battery string loses capacity	Ride-through shorter than assumed	End-of-life margin, individual alarms and replacement plan	Load-conditioned capacity and diagnostic reports
Controller communications are lost	Remote logic unavailable or inconsistent	Local interlocks and defined manual fallback remain functional	Loss-of-link and restoration procedures
Severe thermal or dust exposure	Derating or common cooling outage	Protection, segregation and planned environmental maintenance	Environmental alarms, inspection and periodic revalidation

9. LIMITATIONS, IMPLICATIONS AND CONCLUSION

The principal limitation of this review is evidence transferability. Several informative studies concern hospitals, data centres, campuses or broad distribution networks rather than Saudi industrial sites. Published models also differ in assumed repair resources, load priorities, generator maintenance and outage length; numerical results cannot legitimately be pooled into one predicted facility availability. The source set enables a reasoned architecture and assurance approach, but it cannot resolve manufacturer-specific switching tolerances, site earthing, actual battery ageing or local regulatory approval. Those questions require original engineering data and independent verification.

The central conclusion is that critical building resilience is achieved through a validated continuity chain, not through the presence of backup equipment alone. Redundant UPS paths protect interruption-sensitive loads only when shared failure mechanisms are controlled. Automatic transfer switches support source recovery but must be paired with ride-through where the load cannot tolerate transfer gaps. Generators, batteries, protective devices and maintenance arrangements must be tested as one timed operating system. Applying this layered approach to Saudi Arabia would help designers and facility operators translate infrastructure resilience ambitions into auditable electrical performance, while providing a focused agenda for local field research.

REFERENCES

1. Jasiūnas J, Lund PD, Mikkola J. Energy system resilience: A review. Renewable and Sustainable Energy Reviews. 2021; 150:111476. https://doi.org/10.1016/j.rser.2021.111476
2. Umunnakwe A, Huang H, Oikonomou K, Davis KR. Quantitative analysis of power systems resilience: Standardization, categorizations, and challenges. Renewable and Sustainable Energy Reviews. 2021; 149:111252. https://doi.org/10.1016/j.rser.2021.111252
3. Paul S, Poudyal A, Poudel S, Dubey A, Wang Z. Resilience assessment and planning in power distribution systems: Past and future considerations. Renewable and Sustainable Energy Reviews. 2024; 189:113991. https://doi.org/10.1016/j.rser.2023.113991
4. Zidane TEK, Muis ZA, Ho WS, et al.. Power systems and microgrids resilience enhancement strategies: A review. Renewable and Sustainable Energy Reviews. 2025; 207:114953. https://doi.org/10.1016/j.rser.2024.114953
5. Mohanty A, Ramasamy AK, Verayiah R, et al.. Power system resilience and strategies for a sustainable infrastructure: A review. Alexandria Engineering Journal. 2024; 105:261–279. https://doi.org/10.1016/j.aej.2024.06.092
6. Afzal S, Mokhlis H, Illias HA, Mansor NN, Shareef H. State-of-the-art review on power system resilience and assessment techniques. IET Generation, Transmission & Distribution. 2020; 14(25):6107–6121. https://doi.org/10.1049/iet-gtd.2020.0531
7. Erenoğlu AK, Sengor I, Erdinç O. Power System Resiliency: A Comprehensive Overview from Implementation Aspects and Innovative

Concepts. Energy Nexus. 2024; 15:100311. https://doi.org/10.1016/j.nexus.2024.100311
8. Mishra S, Anderson K, Miller B, Boyer K, Warren A. Microgrid resilience: A holistic approach for assessing threats, identifying vulnerabilities, and designing corresponding mitigation strategies. Applied Energy. 2020; 264:114726. https://doi.org/10.1016/j.apenergy.2020.114726
9. Hamidieh M, Ghassemi M. Microgrids and Resilience: A Review. IEEE Access. 2022; 10:106059–106080. https://doi.org/10.1109/ACCESS.2022.3211511
10. Masrur H, Sharifi A, Islam MR, Hossain MA, Senjyu T. Optimal and economic operation of microgrids to leverage resilience benefits during grid outages. International Journal of Electrical Power & Energy Systems. 2021; 132:107137. https://doi.org/10.1016/j.ijepes.2021.107137
11. Marqusee J, Jenket D. Reliability of emergency and standby diesel generators: Impact on energy resiliency solutions. Applied Energy. 2020; 268:114918. https://doi.org/10.1016/j.apenergy.2020.114918
12. Marqusee J, Ericson S, Jenket D. Impact of emergency diesel generator reliability on microgrids and building-tied systems. Applied Energy. 2021; 285:116437. https://doi.org/10.1016/j.apenergy.2021.116437
13. Zhang L, Yang Y, Li Q, Gao W, Qian F, Song L. Reliability and cost analysis of the integrated emergency power system in building complex. Energy Exploration & Exploitation. 2022; 40(2):501–527. https://doi.org/10.1177/01445987211036824
14. Barnwal R, Clark SW, Yogi B, Balal A. Automatic Transfer Switch for Critical Loads Between Renewables, Storage, Mains, or Generator. 2024 IEEE Texas Power and Energy Conference. 2024; pp. 1–5. https://doi.org/10.1109/TPEC60005.2024.10472269
15. IEEE Standards Association. IEEE Guide for Batteries for Uninterruptible Power Supply Systems (IEEE Std 1184-2022). IEEE. 2022; Standard 1184-2022. https://doi.org/10.1109/IEEESTD.2022.9774336
16. Bolsi PC, Prado EO, Lima ACC, Sartori HC, Pinheiro JR. Battery autonomy estimation method applied to lead–acid batteries in uninterruptible power supplies. Journal of Energy Storage. 2023; 58:106421. https://doi.org/10.1016/j.est.2022.106421
17. Huang LL, Wang ZW, Xu HR, Wang BL, Chen WW. FMEA-based risk mitigation for hospital UPS failures. Results in Engineering. 2025; 27:106833. https://doi.org/10.1016/j.rineng.2025.106833
18. VanZwol J. Chemistry Options for Lithium-Ion UPS and BBU [Expert View]. IEEE Power Electronics Magazine. 2022; 9(1):48–50. https://doi.org/10.1109/MPEL.2021.3139254
19. Lystianingrum V, Priyadi A, Negara IMY. Lessons learned from large-scale lithium-ion battery energy storage systems incidents: A mini review. Process Safety Progress. 2023; 42(2):348–355. https://doi.org/10.1002/prs.12448
20. Wei J, Liang F, Feng H, Ran L. Condition Monitoring of Discrete Power Devices: A Data-Driven Approach With Stress Quantification and Mold Temperature Sensing. IEEE Journal of Emerging and Selected Topics in Power Electronics. 2024; 12(3):2569–2579. https://doi.org/10.1109/JESTPE.2024.3387652
21. Barani M, Vadlamudi VV, Heegaard PE. Reliability analysis of cyber-physical microgrids: Study of grid-connected microgrids with communication-based control systems. IET Generation, Transmission & Distribution. 2021; 15(4):645–663. https://doi.org/10.1049/gtd2.12049
22. Magoua JJ, Wang F, Li N. High level architecture-based framework for modeling interdependent critical infrastructure systems. Simulation Modelling Practice and Theory. 2022; 118:102529. https://doi.org/10.1016/j.simpat.2022.102529
23. Bellè A, Zeng Z, Duval C, Sango M, Barros A. Modeling and vulnerability analysis of interdependent railway and power networks: Application to British test systems. Reliability Engineering & System Safety. 2022; 217:108091. https://doi.org/10.1016/j.ress.2021.108091
24. Alsubaie HT. The Development of a Hybrid Microgrid System to Improve the Robustness of Electrical Services in Al Uyaynah City, Saudi Arabia. Advances in Transdisciplinary Engineering. 2024; https://doi.org/10.3233/ATDE240350
25. Al-Sharif YM, Sowilam GM, Kawady TA. Harmonic Analysis of Large Grid-Connected PV Systems in Distribution Networks: A Saudi Case Study. International Journal of Photoenergy. 2022; 2022:8821192. https://doi.org/10.1155/2022/8821192
26. Hervás-Zaragoza J, Colmenar-Santos A, Rosales-Asensio E, Colmenar-Fernández L. Microgrids as a mechanism for improving energy resilience during grid outages: A post COVID-19 case study for hospitals. Renewable Energy. 2022; 199:308–319. https://doi.org/10.1016/j.renene.2022.08.132
27. Wang Z, Yin Z, Yang J, Wang J. Coordinated optimization of distributed energy system and storage-enhanced uninterruptible power supply

in data center: A three-level optimization framework with model predictive control. Energy Conversion and Management. 2025; 342:120137. https://doi.org/10.1016/j.enconman.2025.120137

28. Mishra DK, Eskandari M, Abbasi MH, et al.. A detailed review of power system resilience enhancement pillars. Electric Power Systems Research. 2024; 230:110223. https://doi.org/10.1016/j.epsr.2024.110223
29. Ptak T, Brooks J, Stock R. A systematic review and typology of power outage literature: Critical infrastructure, climate change and social impacts. Renewable and Sustainable Energy Reviews. 2025; 218:115778. https://doi.org/10.1016/j.rser.2025.115778
30. Uddin M, Mo H, Dong D, Elsawah S, Zhu J, Guerrero JM. Microgrids: A review, outstanding issues and future trends. Energy Strategy Reviews. 2023; 49:101127. https://doi.org/10.1016/j.esr.2023.101127.